



PLANT SUMMARY

TREES	KEY	SCIENTIFIC NAME	COMMON NAME	SIZE	HGT	STAKING	REMARKS
	T1	QUERCUS ALBA	WHITE OAK	3" CAL.	14'-16'	DETAIL B	
	T2	QUERCUS MICHAUXII	SWAMP CHESTNUT OAK	3" CAL.	14'-16'	DETAIL B	
	T3	QUERCUS FALCATA	SOUTHERN RED OAK	3" CAL.	14'-16'	DETAIL B	
	T4	QUERCUS FALCATA 'SHUMARDI'	SHUMARD OAK	3" CAL.	14'-16'	DETAIL B	
	T5	ILEX OPACA 'SAVANNAH'	SAVANNAH HOLLY	1" CAL.	8'-10'	DETAIL A	

NOTES:
 1. TREES SHALL BE BALLED AND BURLAPPED.
 2. HEIGHT PRECEEDS CALIPER. SHOULD INDICATED CALIPERS BE LESS THAN INDUSTRY STANDARDS, THEN CONTRACTOR SHALL PROVIDE MATERIAL TO THE HEIGHT SPECIFIED W/ STANDARD INDUSTRY CALIPERS.
 3. TREE STAKING DETAIL 'B' SHALL BE USED FOR TREES T1, T2, T3, AND T4. UNLESS AVAILABLE RIGHT-OF-WAY DOES NOT ALLOW UTILIZATION OF TREE STAKING DETAIL 'A' SHALL BE ACCEPTABLE UPON APPROVAL BY LANDSCAPE ARCHITECT.
 4. ○ SYMBOL AT CENTER OF TREE INDICATES TREES ADDED TO BASE BID AS A UNIT PRICE ITEM.
 5. LANDSCAPE EASEMENT LOCATIONS HAVE BEEN PROVIDED BY THE OWNER. LANDSCAPE EASEMENTS ARE 15 FEET WIDE.

